



## German Red Cross, Bangladesh

### BoQ

#### Bill of Quantity for Handwashing station at School level\_Teknaf

Sl	Description	Quantity	Unit	Unit Price	Amount
1	Earth cutting/Excavation work and levelling	90	Sft		
2	Sand (Filling)	100	cft		
3	Brick Soling with first class bricks (9.5"X4.5"X2.75")	115	Sft		
4	CC work with jhama picket brick chips(Ratio should be 1:2:4)	35	cft		
5	10" Brick work with net cement finishing Quality of bricks should be first class (9.5"X4.5"X2.75"). Ratio should be 1:4	15	cft		
6	5" Brick work with net cement finishing Quality of bricks should be first class (9.5"X4.5"X2.75"). Ratio should be 1:4	115	Sft		
7	Sus 304 Water Tap/faucet (SS) as per photo (235*100*80mm)	14	Nos		
8	Floor Tiles (12" X 12"). It should be RAK or equivalent	50	Sft		
9	Wall tiles (8"X 12"). It should be RAK or equivalent	125	Sft		
10	Fittings and Fixing (GI). This is for all kind of pipe network activity.	1	LS		
11	1.25" dia PVC Thread pipe/ Distribution pipe	100	ft		
12	Thread tape/Teflon tape	12	Nos		
13	White cement	3	Kg		
14	Polyethene	2	kg		
15	3' dia Ring (1.5" thickness and 1 feet height). It should be well bonding and made by picket.	4	pcs		

16	3' dia Ring slab (1.5" thickness).It should be well bonding and made by picket.	1	pcs		
17	2" dia 2.5 - 2.70 mm thick class-D drainage pipe. The selected vendor should connect the pipe to discharge the wastage water.	45	ft		
18	2" plastic Elbow for drainage connection	8	pcs		
19	2" plastic Tee for drainage connection	3	pcs		
20	Corrugated light transparent Plastic sheet 10'-0" long and 32" width and 1.5mm thickness	6	pcs		
21	1.5" dia 3mm thick GI hollow pipe for roof pole and ridge with well galvanized and all joint should be running weilding or nut-bolt.	50	ft		
22	1.5" X1.5"angle bar with 3mm thickness for roof frame (rafter and purlin) with well galvanized and all joint should be running weilding or nut-bolt.	100	ft		
23	Different fittings for placing the plastic sheet	1	LS		
24	Head carrying cost	1	LS		
				<b>Total</b>	
				<b>Grand Total for 26</b>	
<b>In Word:</b>					

All unit prices are without VAT and including TAX.

Validity of Quotation minimum 180 day from the deadline for submission.

Delivery time (Materials Mobilization & time of completion of delivery):

Location: 20 Schools in 6 Unions at Teknaf, Cox's Bazar

**Date of Quotation:**

**Stamp and Signature of Bidder**