

German Red Cross, Bangladesh

BoQ

Bill Of Quantities (BoQ) for the drainage construction (camp-13 & 18 in kutupalong, Ukhia, Cox's bazar)

Item	Description	Unit	Quantity	Unit Price	Amount
1	Earth cutting/Excavation work	1350.0	cubic metre		
2	PCC work (1:2:4): PCC work with net finishing for bottom of the drainage as per direction of engineer in charge. Brick chips should be 1st class Jhama picket and size should not be less than 0.013 m (1/2") and greater than 0.019 m (3/4"). All cost should be including carrying and labor.	343.0	cubic metre		
3	0.13 m (5")Brick works with 0.012m (1/2") plaster (Ratio 1:4) with net finishing as per the direction of assigned engineer in charge. Bricks should be 1st class and cement should be a well known company. All cost should be including carrying and labor.	3603.0	square metre		
4	0.254 m (10") Brick works with 0.013m (1/2") plaster and net finishing as per the direction of assigned engineer in charge. Bricks should be 1st class and sand F.M not less than 1.2. All cost should be including carrying and labor.	29.0	cubic metre		
5	Polyethene for placing below PCC work	3660.0	square metre		
Sub Total					
6	Materials mobilization cost from road side to construction site	1.0	LS		
Grand Total					
In Word:					
Note: The dimension and volume of drainage construction work may be fluctuate during construction because of location, slope and topography of road way. BDRCS/GRC will pay the bill after justification of actual work.					

All unit prices are without VAT and including TAX.

Validity of Quotation minimum 120 day from the deadline for submission.

The maximum time is 2 Months to completion of works after issuing the work order.

Delivery time (Materials Mobilization & time of completion of delivery):

Date of Quotation:

Stamp and Signature of Bidder