

**German Red Cross Bangladesh**  
**Bill of Quantity for Handwashing station in Camp 13 & 18**



SI No	Description of Item	Quantity	Unit	Unit Price (BDT)	Total Amount (BDT)
1	<b>Earth Excavation:</b> Earth work in excavation in all kinds of soil for foundation trenches including; providing center lines, leveling, preparing the base as per attached drawing & instruction GRC/BDRCS Engineer incharge.	15.00	cft		
2	<b>Sand Filling:</b> Sand filling with local sand and well compaction as per attached drawing & instruction GRC/BDRCS Engineer incharge.	12.00	cft		
3	<b>RCC RING:</b> RCC ring with 36 inch inner dia, thickness 2 inch, 1 ft height, Both of the ring need to be joined with cc when placing in the site to avoid water leakage.	2.00	nos		
4	<b>CC Work for Base of Stand :</b> CC casting the Base of Hand Washing Stand [recommended mixing proportion 1:2:4] using picked jhama chips, including supply, screening, washing, mixing, laying, compacting to levels and curing for at least 7 days including the supply of water, electricity and other charges and costs of tools etc. all complete and accepted by the GRC/BDRCS Engineer in-charge. (Cement: Scan/Rubi)	0.70	cft		
5	<b>MS Angle Bar for Hand washing Stand with wash basin:</b> Supply, Fitting, Fixing and welding of MS Angle (BSRM orequivalent branded) Stand (38 mmx38 mmx 4 mm) and <b>flat bar (38mmX38mmX4mm and 25mmX25mmX3mm)</b> . Wash basin & soap case connected with the frame. 2 inch MS flat bar with 4mm thickness attached on the top of the frame where at one side there will be hinge and another side there should be anchor and provision for lock. medium size lock and key will be provided by the supplier. Red anti-rust or corrosion color on the materials as per attached drawing & instruction GRC/BDRCS Engineer incharge.	20.00	kg		
6	<b>Brick Chips :</b> Using picked jhama chips (3/4 down), including supply, screening, washing other charges and costs of tools and plants etc. all complete and accepted by the GRC/BDRCS Engineer in-charge.	7.00	cft		
7	<b>PVC Drum With Tap:</b> Supplying & fitting the Good Quality PVC Drum with lid & tap(60 liter) volumn With fitting PVC Tap including Jum not must be Steel. with one additional separate pvc tap.	1.00	L.S		
8	<b>PVC Pipe:</b> 4 inch uPVC Pipe for drainage of stagnant water where necessary.	10.00	rft		
9	<b>Visibility / stickers:</b> Prepare and fixing of Visibility stickers of BDRCS, GRC, IFRC & MoFA as per given design and color code, print the information and logoes over size of stickers 1'x 8" A4	1	nos		
<b>Total Amount for One unit (Hand Washing Facility)</b>					
<b>Total Amount for 500 units (Hand Washing Facility)</b>					

**All unit prices are including TAX and without VAT.**

**Validity of this quotation until 31 December 2020.**

**Delivery time (lead time, time of completion of delivery) :**

**Date of Quotation:**

**Stamp and Signature of Bidder**