Annex-10
BOQ of Repairing Work:-Solar Ceiling Fan, Table Fan, solar Lights . Boundary, Walkway and Drainage system
Location:- Camp-25 , Alikhali-1(MPC), Blue Star Leda, Teknaf

Sl No.	Description	Unit / Form	Quantity	Unit Price	Currency	Total Amount
A	**Electrical -Electronic Repairing:- Alikhali-1 (Blue Star)**					
1	**Repair, Fitting and fixing of Three no of Ceiling Fan with Technician Charges**	**Package**	1		BDT	
2	**Supply, Fitting and fixing of Two Solar Light(5 Watt) with Holder, wire etc. all complete**	**Set**	2		BDT	
B	**Boundary FenceWorks (225 Rft) with Entry Gate.**					
1	Supply:- 3" Borak bamboo (20 ' long)) for 47 no of 8feet long boundary Column .	PC	11		BDT	
2	Supply:- 3" Borak bamboo (20 ' long)) for boundary horizantal Member {870 rft} (Bottom-Middle and Top) .	PC	34		BDT	
3	Supply:-18 BWG GI Wire Net .	SFT	1125		BDT	
4	Supply:-22 BWG GI Wire .	KG	8		BDT	
5	Cutting , Fitting and Fixing Labour Charges	**No.**	12		BDT	
C	**Drainage (10''x 10'' x150')**					
1	**Single layer BFS (250 Sft) with 3'' sand filling , Cement morter bonding with NCF (110'x1.25''') as per EIC direction**					
a	Supply:- Brick	**Pc.**	800		BDT	
b	Supply:- Sand	**Cft**	65		BDT	
c	Supply:- Cement	**Bag**	4		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	8		BDT	
2	**5" Brick work(1:5) with Both side Plaster (1:4) with NCF (Total Area 150' x10'')=300 Sft**					
a	Supply:- Brick	**Pc.**	1500		BDT	
b	Supply:- Sand	**Cft**	15		BDT	
c	Supply:- Cement	**Bag**	12		BDT	

d	Cutting , Fitting and Fixing Labour Charges	**No.**	20		BDT	
D	**Walk way (375 Sft)** **Supply and fitting with labour cost:** Single layer BFS with 3" sand filling , Cement morter bonding with NCF (125'x3') as per EIC direction					
1	Supply:- Brick	**Pc.**	1200		BDT	
2	Supply:- Sand	**Cft**	70		BDT	
3	Supply:- Cement	**Bag**	9		BDT	
4	Cutting , Fitting and Fixing Labour Charges	**No.**	16		BDT	
E	Total Material's carrying, loading and unloading charges	**Package**	1		BDT	
	Inc. Vat and Tax				**Total Cost:-**	