Annex-6

BOQ of Repairing Work:-Solar Ceiling Fan, Table Fan, solar Lights . Boundary, Walkway and Drainage system

Location:- Camp-25 , Alikhali-2(MPC)-Joba, Leda, Teknaf

Sl No.	Description	Unit / Form	Quantity	Unit Price	Currency	Total Amount
A	**Electrical -Electronic Repairing:- Alikhali-2 (Joba)**					
1	**Repair, Fitting and fixing of Two no of Ceiling Fan with Technician Charges**	**Package**	1		BDT	
2	**Supply, Fitting and fixing of Two Solar Light(5 Watt) with Holder, wire etc. all complete**	**Set**	2		BDT	
B	**Structure's Floor (30' x 2o') :-3'' CC casting**					
1	**Supply:- 3/4'' Brick Chips**	**Cft**	129		BDT	
2	**Supply:- Sand**	**Cft**	65		BDT	
3	**Supply:- Cement**	**Bag**	26		BDT	
4	**Cutting ,Fitting and Fixing Lobour Charges**	**Nos**	10		BDT	
C	**Boundary FenceWorks (225 Rft) Entry Gate.**					
1	Supply:- 3" Borak bamboo (20 ' long)) for 47 no of 7feet long boundary Column .	PC	8		BDT	
2	Supply:- 3" Borak bamboo (20 ' long)) for boundary horizantal Member {675 rft} (Bottom-Middle and Top) .	PC	34		BDT	
3	Supply:-18 BWG GI Wire Net .	SFT	1125		BDT	
4	Supply:-22 BWG GI Wire .	KG	8		BDT	
5	Cutting , Fitting and Fixing Labour Charges	**No.**	12		BDT	
D	**Drainage (10''x 10'' x150')**					
1	**Single layer BFS (250 Sft) with 3'' sand filling , Cement morter bonding with NCF (110'x1.25''') as per EIC direction**					
a	Supply:- Brick	**Pc.**	800		BDT	
b	Supply:- Sand	**Cft**	65		BDT	
c	Supply:- Cement	**Bag**	4		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	8		BDT	
2	**5" Brick work(1:5) with Both side Plaster (1:4) with NCF (Total Area 150' x10'')=300 Sft**					
a	Supply:- Brick	**Pc.**	1500		BDT	
b	Supply:- Sand	**Cft**	15		BDT	

c	Supply:- Cement	**Bag**	12		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	20		BDT	
E	**Walk way (210Sft)** **Supply and fitting with labour cost:** Single layer BFS with 3" sand filling , Cement morter bonding with NCF (125'x3') as per EIC direction					
1	Supply:- Brick	**Pc.**	1000		BDT	
2	Supply:- Sand	**Cft**	55		BDT	
3	Supply:- Cement	**Bag**	6		BDT	
4	Cutting , Fitting and Fixing Labour Charges	**No.**	16		BDT	
F	**Total Material's carrying, loading and unloading charges**	**Package**	1		BDT	
	Inc. Vat and Tax				**Total Cost:-**	