Annex-18
BOQ for Boundary fence support,Tarpaulin Covering and Walkway .
Location- Camp-17, QQ-WGFS

S/N	Descriptions	Unit / Form	Quantity	Unit Price	Currency	Total Amount
A	**Boundary Tin Fence support Column :-**					
1	Supply, fitting with Labour : 3" borak Bamboo	Pc.	25		BDT	
2	Supply, fitting with Labour : 18 SWG GI Wire	Kg.	10		BDT	
3	Cutting, Fitting and fixing labour chrges	No.	6		BDT	
B	**Bamboo Fence (Structure) covering :-**					
1	Supply, fitting with Labour : 0.018 mm Tarpaulin (12'x18')	Pc.	12		BDT	
2	Supply, fitting with Labour : 1.5" dia and 15' long Muli Bamboo for Tarpaulin holding porpose.	Pc.	35		BDT	
3	Supply, fitting with Labour : 3mm Nylon rope	Kg.	3		BDT	
4	Cutting, Fitting and fixing labour chrges	No.	4		BDT	
C	**240 sft. Walkway (80' x3'): Single Layer BFS including 4" Sand Filling with Cement mortar bonding and Plastering with Neat Cement Finished.**					
1	Supply :- Cement	Bag	6		BDT	
2	Supply :- Brick	Pc.	1200		BDT	
3	Supply :- Sand	Cft	120		BDT	
4	Cutting, Fitting and fixing labour chrges	No.	10		BDT	
D	**Land Preparation :-**					
1	Exixting earth cutting , leveling , Bag fillingwith soil and dumping :- Labour .	No.	8		BDT	
2	Supply New Plastic Bag (Cement) :	Pc.	100		BDT	
				Total Cost		