Annex-2

BOQ of Repairing Work:- Solar Ceiling Fan, Table Fan, ar Lights and Boundary and Floor.

Location:- Camp-27 (MPC), JADIMURA, Teknaf

Sl No.	Description	Unit / Form	Quantity	Unit Price	Currency	Total Amount
A	**Electrical -Electronic Repairing:- Alikhali-1 (Blue Star)**					
1	Repair, Fitting and fixing of Three no of Ceiling Fan ,Switch Board with Technician Charges	Package	1		BDT	
2	Repair, Fitting and fixing of Two no of Stand Fan with Technician Charges	Package	1		BDT	
3	Supply, Fitting and fixing of Two Solar Light(5 Watt) with Holder, wire etc. all complete	Set	2		BDT	
B	**Boundary FenceWorks (182 Rft) with Entry Gate.**					
1	Supply:- 3" Borak bamboo (20 ' long)) for 38 no of 8 feet long boundary Column .	PC	38		BDT	
2	Supply:- 3" Borak bamboo (20 ' long)) for boundary horizantal Member {546 rft} (Bottom-Middle and Top) .	PC	28		BDT	
3	Supply:-18 BWG GI Wire Net (6 feet wide)	SFT	1092		BDT	
4	Supply:-22 BWG GI Wire .	KG	8		BDT	
5	Cutting , Fitting and Fixing Labour Charges	No.	15		BDT	
C	**Land Protection at West side (50 feet long)**					
1	Supply:- 3" Borak bamboo (20 ' long)) for 20 no of 8 feet long Column .	PC	10		BDT	
2	Supply:- 3" Borak bamboo (20 ' long)) for Dram support horizantal Member {150 rft} (Bottom-Middle and Top) .	PC	23		BDT	
3	Supply:- Dram sheet .	PC	25		BDT	
4	Cutting , Fitting and Fixing Labour Charges	No.	15		BDT	
D	**Flooring:- (31' x22'=682 Sft)**					
1	**Mass concrete(31 x22' x3''= 170 Cft.) casting(1:2:4) for Activity Floor NCF finished as per EIC direction.**					
a	Supply:- 3/4" size Brick Chips	Cft	142		BDT	
b	Supply:- Sand	Cft	75		BDT	
c	Supply:- Cement	Bag	30		BDT	
d	Cutting , Fitting and Fixing Labour Charges	No.	25		BDT	
E	**Total Doneted Material's carrying, loading and unloading charges at site.**	Package	1		BDT	
	Inc. Vat and Tax				**Total Cost:-**	