BOQ of Repairing Work:- Boundary,Structure 's Column andFloor CC Casting .
Location:- Camp-18 -SS (MPC)

Sl No.	Description	Unit / Form	Quantity	Unit Price	Currency	Total Amount
A	Boundary Fence:-(180 Rft)					
1	Supply:3'' Borak Bamboo(20' Long) as Column {8 feet size}	PC	15		BDT	
2	Supply:3'' Borak Bamboo(20' Long) as Horizantal Batton	PC	27		BDT	
3	Supply: 18 BWG GI Net (5' Wide)	Sft	900		BDT	
4	Supply: 20gauge GI Wire	Kg	8		BDT	
5	Cutting ,Fitting and Fixing Lobour Charges	Nos	10		BDT	
B	Structure's Column:-					
1	Supply:- 3'' Borak Bamboo(20' Long) as Column .	PC	10		BDT	
2	Supply:- 6 mm Nylon Rope	Kg	5		BDT	
C	Structure's Floor (30' x 2o') :-3'' CC casting					
1	Supply:- 3/4'' Brick Chips	Cft	129		BDT	
2	Supply:- Sand	Cft	65		BDT	
3	Supply:- Cement	Bag	26		BDT	
4	Cutting ,Fitting and Fixing Lobour Charges	Nos	10		BDT	
D	Window Repairing (Case Management)	Package	1		BDT	
E	Total Carrying, Lifting, Loading/Unloading of Donated items to site.	Package	1		BDT	
	Inc. Vat and Tax				Total Cost:-	