Annex-16

BOQ of Community Structure's Damage Repair and New Extension Works.

Location:- Camp 27,Counciling Center, Jadimura,Teknaf

S/N	Descriptions	Unit / Form	Quantity	Unit Price	Currency	Total Amount
A	**Window Wire Net(58' x2.5'=145sft) :-**					
1	Supply :- 1"x1" Wire Mesh	SFT	145		BDT	
2	Supply, fitting and Fixing :- Wood (2" x1" x8' x 10pc)=	CFT	1.12		BDT	
3	Supply fitting with Labour :- Nail (0.5", 1.5" size)	KG	1		BDT	
4	Supply fitting and Fixing :- Water seal Putty for sealing of rain water from Tin roof.	Packet	35		BDT	
5	Labour Cost	No.	8		BDT	
B	**Bamboo fence covering (L-85 ' x W-9'')=765 Sft.**					
1	Supply fitting and Fixing :- Tarpolin	SFT	765		BDT	
2	Supply fitting and Fixing :- Muli Bamboo (15' long size)	PC	15		BDT	
3	Supply fitting and Fixing :- 20 SWG GI Wire	Kg	1		BDT	
	Supply fitting and Fixing :- 6mm Nylon Rope	Kg	1		BDT	
4	Cutting,fitting and Fixing labour Charges	No.	3		BDT	
C	**Structure's Extension Works (20.5'x 17.5')=377sft**					
1	At Foundation 1.25' wide BFS with 3" sand filling (103 feet long)	Sft	130		BDT	
2	Labour Charges	No.	8		BDT	
D	Foundation, Wall and floor 1) 10" Brick foundation with Plaster and NCF (103' x.1.5')=155 Sft 2) 5" Brick Wall 3 feet high surrounding facility. (103' x.1.5')=155 Sft, with Plaster and NCF finished. 3) At Floor (377 Sft) , BFS with cement morter, Plaster with NCF Finished. 4) 3" CC casting(40 Cft) with plaster and NCF Finished					
1	Supply :-Brick	Pc	4200		BDT	
2	Supply :-Cement	Bag	20		BDT	

3	Supply :-Sand	Cft	300		BDT	
4	Supply :-0.75 " Brick Chips	Cft	50		BDT	
5	Labour Charges	No.	30		BDT	
E	**Metal Column:-**					
1	3" dia, Metal pipe (3mm plate thickness)	Rft	170		BDT	
2	**(1 'x 1 'x 2') column Base CC casting(30 Cft)**				BDT	
a	supply :- Cement	Bag	6		BDT	
b	supply :- 0.75 size brick chips	Cft	30		BDT	
c	supply :- Sand	Cft	15		BDT	
d	Labour Charges	No.	8		BDT	
F	**Metal Trass (Rufter and Parlin):-**					
1	4mm plate Thickness 2" x2" Angle	Rft	450		BDT	
2	Cutting, Fitting and Fixing Labour Charges	No.	20		BDT	
G	**0.46mm thick galvanized color CI sheet**	Bundle	3.5			
1	"J" Hook	Pc	210		BDT	
2	Cutting, Fitting and Fixing Labour Charges	No.	20		BDT	
H	Heat Insulation Sheet for Side Fence and Roof	Sft	700		BDT	
1	Cutting Fitting and fixing labour charges	No.	10		BDT	
I	Wooden Door and Windows					
1	Door (3'-3" x 7')	Pc	3		BDT	
2	Window	Pc	5		BDT	
3	Cutting, Fitting and Fixing Labour Charges	No.	12		BDT	
J	Toilet Set(Low comode and basin) with plumbing	Package	1		BDT	
1	Cutting Fitting and fixing labour charges	No.	6		BDT	
K	Electrical Fittinga and Fixtures	Package	1			
	Inc Vat & Tax			**Total Cost**		