Annex-1
BOQ for Repairing Work of Foundation, Roof, Entry Door, Bamboo FenceTwo Fan Two Lights and Floor Casting. Location:- Camp-26 MPC

S/N	Description	Unit	Quantity	Unit Price	Currency	Total Prices
A	**Foundation :-(104 Rft)-Structure Size-30'x 22'=660Sft**					
1	**Supply :** labour cost: Foundation layout and earth cutting.	**Package**	**1**		BDT	
2	**Single layer BFS with 3'' sand filing.(104' x 15'')=130 Sft.with Cement Bonding as per EIC direction.**					
a	Supply:- Brick	**Pc.**	400		BDT	
b	Supply:- Sand	**Cft**	35		BDT	
c	Supply:- Cement	**Bag**	3		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	8		BDT	
3	**10'' Brick wall (260sft) 2.5' high and 104 feet long. 1.5' under the ground and rest 1' at plinth level.**					
a	Supply:- Brick	**Pc.**	2900		BDT	
b	Supply:- Sand	**Cft**	75		BDT	
c	Supply:- Cement	**Bag**	11		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	30		BDT	
4	**1'-3" wide and 118 long Single layer (130 Sft) BFS ,with 3" Sand Filling at surrounding structure's area.for protection of the plinth with Cement Bonding as per EIC direction.**					
a	Supply:- Brick	**Pc.**	530		BDT	
b	Supply:- Sand	**Cft**	70		BDT	
c	Supply:- Cement	**Bag**	5		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	24		BDT	

5	**5" Brick work with Both side NCF(Total Area 104' x 2.5'=260Sft)with both side palster and NCF.**					
a	Supply:- Brick	**Pc.**	1300		BDT	
b	Supply:- Sand	**Cft**	60		BDT	
c	Supply:- Cement	**Bag**	6		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	25		BDT	
B	**Flooring:- (35' x22'=770 Sft)**					
1	Supply and fitting with labour cost:-Compact sand(Viti balu) filling. [35' x22' x1.5']	**Cft**	1155		BDT	
2	Supply and fitting with labour cost:- Single layer BFS with 3" sand filing.(35' x 22')	**Sft.**	770		BDT	
3	Mass concrete(35' x22' x3"= 193 Cft.) casting(1:2:4) for Activity Floor NCF finished as per EIC direction.					
a	Supply:- 3/4" size Brick Chips	**Cft**	166		BDT	
b	Supply:- Sand	**Cft**	85		BDT	
c	Supply:- Cement	**Bag**	33		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	25		BDT	
C	**Structure's Bamboo Column:-(30 Pc)**					
1	Supply:-3" Borak bamboo as column (12' long)	Pc	15		BDT	
2	Supply:-3' long "Y' Clamps to grip Bamboo Column with Nut-Bolt	Pc	30		BDT	
3	Supply:-6"Long 12mm Nut & Bolt	Pc	60		BDT	
2	Mass concrete casting(1:2:4) for 30 no of Column foundation bottom as per EIC direction. (1'x1'x2')	CFT	60		BDT	
a	Supply:- 3/4" size Brick Chips	**Cft**	52		BDT	
b	Supply:- Sand	**Cft**	26		BDT	
c	Supply:- Cement	**Bag**	10		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	20		BDT	
D	**New Roof (33' x25') Construction**					

1	**Supply:-3'' Borak Bamboo as Rufter**	PC	20		BDT	
2	**Supply:-** 1.5" Muli Bamboo as Purlin	Pc	100		BDT	
3	**Supply:-** 1.5" Muli Bamboo as 6"x6" gridding bamboo chata	Pc	60		BDT	
4	**Supply:-** Sun Grass	Bundle	20		BDT	
5	**Supply:-** .018 mm Tarpaulin	Sft	900		BDT	
6	**Supply:-** .3mm and 6 mm Nylon Rope	Kg.	6		BDT	
7	Cutting , Fitting and Fixing Labour Charges	**No.**	20		BDT	
E	**7 feet wide Bamboo Weave Outer Fence(104' long) and All Iner Partition (60' Long) =1148 Sft**					
1	Supply:-Bamboo weave dauna	Sft	1148		BDT	
2	Supply:- 1.5" Muli Bamboo as Purlin	Pc	70		BDT	
5	Supply:- .018 mm Tarpaulin (110 feet long and 8 feet wide) for 4 Side covering	Sft	832		BDT	
6	Supply:- .3mm and 6 mm Nylon Rope	Kg.	6		BDT	
7	Cutting , Fitting and Fixing Labour Charges	**No.**	20		BDT	
F	**Door**					
1	**Supply and fitting with labour cost:** Door (0.33mm Blue iron sheet,wooden frame,hinges,nails,Hasbolt) (Toilet 3.0'x7') as per EIC direction	PC	1		**BDT**	
G	**Boundary FenceWorks (162 Rft)**					
1	Supply:- 3" Borak bamboo (20 ' long)) for 60 no of boundary Column (8' Long)	PC	13		BDT	
2	Supply:- 3" Borak bamboo (20 ' long)) for boundary horizantal Member {870 rft} (Bottom-Middle and Top) .	PC	25		BDT	
3	Supply:-18 BWG GI Wire Net .	SFT	972		BDT	
4	Supply:-22 BWG GI Wire .	KG	8		BDT	
5	Cutting , Fitting and Fixing Labour Charges	**No.**	8		BDT	
H	Electrical				BDT	
1	Supply , fitting fixing of two no. solar Fan with Technician Charges	**Package**	1		BDT	
I	**Total doneted Item's carrying, Lifting, Loading/Unloading at site.**	**Package**	1		BDT	
	Inc. Vat & Tax				**Total Cost**	