Annex-9
Repairing works of Structure Boundary, Walkway, Partly foundation Protection.
Location:- AA-Down MPC (Waterlily)

S/N	Descriptions	Unit / Form	Quantity	Unit Price	Currency	Total Amount
A	**Boundary Fence(120 feet long) (MS Pipe,Angla and Wire Mesh)**					
1	Supply :- :2" dia and 9 feet long MS pipe (3mm plate thickness) as Column-(25pc)	RFT	225		BDT	
2	Supply: :CC Column Base (1'x 1' x2')	CFT	50		BDT	
a	Supply Brick Chips	Cft	45		BDT	
b	SupplySand	Cft	20		BDT	
c	Supply Cement	Bag	8		BDT	
3	Supply :- 0.18 SWG GI Wire Net	Sft	720		BDT	
4	Supply and fitting with Labour cost :1.5" x1.5" Angle (4 mm plate thickness) for horizantal support at top, middle and bottom.with 2 no of entry gate.	RFT	380		BDT	
5	Supply and fitting with Labour cost :"J"Hook with nut for fixing up Dhewtin with angls.	PC	400		BDT	
6	Supply : Drum Sheet for Soil protection	PC	20		BDT	
7	Supply Compact sand	Cft	200		BDT	
8	Supply :3" Borak Bamboo for short column, Horizantal Part	PC	25		BDT	
9	Supply : 20 SwG GI Wire	Kg	4		BDT	

10	Cutting, Fitting Fixing Labour Charges	No	20		BDT	
B	Walk way (25' x 4')=100				BDT	
1	Supply Brick Brick Flat Soling with 3" Sand Filing	Pc	600		BDT	
2	Supply Sand	Cft	40		BDT	
3	Supply Cement for BFS bonding with plastering	Bag	7		BDT	
4	Cutting, Fitting Fixing Labour Charges	No	10		BDT	
C	Roof				BDT	
1	Supply Tarpaulin	Sft	770		BDT	
2	Supply 6mm Nylon Rope	Kg	5		BDT	
3	Supply Muli Bamboo	Pc	40		BDT	
4	Supply 3"Borak Bomboo	Pc	6		BDT	
	Inc Vat & Tax			**Total Cost**		