# Annex-14
# BOQ for Reconstruction Work of 8W- WGFS, Camp-8W,Ukhiya

| S/N | Description | Unit | Quantity | Unit Price | Currency | Total Prices |
|---|---|---|---|---|---|---|
| | **Civil Work Items:** | | | | | |
| **A** | **Foundation :-** | | | | | |
| **1** | **Supply :** labour cost: Foundation layout and earth cutting. | **Package** | **1** | | BDT | |
| **2** | **Supply and fitting with labour cost:-** Single layer BFS with 3" sand filing.(125' x 15")=157sft. | | | | | |
| **a** | Supply:- Cement | **Bag** | 4 | | BDT | |
| **b** | Supply:- Sand | **Cft** | 35 | | BDT | |
| **c** | Cutting ,fitting and fixing labour charges | **No.** | 6 | | BDT | |
| **B** | **Supply and fitting with labour cost:-10'' Brick wall 2' high and 125 feet long. (one feet under the ground and rest 1' at plinth level.** | **Sft.** | 171 | | BDT | |
| **1** | **Supply:-Brick** | **Pc.** | 3000 | | BDT | |
| **2** | **Supply:- Cement** | **Bag** | 11 | | BDT | |
| **3** | **Supply:- Sand** | **Cft** | 65 | | BDT | |
| **4** | **Cutting ,fitting and fixing labour charges** | **No.** | 25 | | BDT | |
| **C** | **Supply and fitting with labour cost:** 1'-3" wide and 125 long Single layer BFS ,with 3" Sand Filling at surrounding structure's area.for protection of the plinth as per EIC direction. | SFT | 759 | | BDT | |
| **1** | Supply:-Brick | Pc. | 500 | | BDT | |
| **2** | Supply:- Cement | Bag | 3 | | BDT | |
| **3** | Supply:- Sand | Cft | 25 | | BDT | |
| **4** | Cutting ,fitting and fixing labour charges | No. | 14 | | BDT | |

| | | | | | | |
|---|---|---|---|---|---|---|
| **D** | **Supply and fitting with labour cost:5" Brick work with Both side NCF(Total Area 125' x 2.5')= 315Sft.** | | | | | |
| **1** | Supply:-Brick | Pc. | 1600 | | BDT | |
| **2** | Supply:- Cement | Bag | 7 | | BDT | |
| **3** | Supply:- Sand | Cft | 50 | | BDT | |
| **4** | Cutting ,fitting and fixing labour charges | No. | 20 | | BDT | |
| **E** | **Flooring:- (35' x22')** | | | | | |
| 1 | **Supply and fitting with labour cost:-**Compact sand( Viti balu) filling. [35' x22' x1'] | **Cft** | 770 | | BDT | |
| 2 | **Supply and fitting with labour cost:-** Single layer BFS with 3" sand filing.(35' x 22') | **Sft.** | 770 | | BDT | |
| **a** | Supply:-Brick | **Pc.** | 2500 | | BDT | |
| **b** | Supply:- Cement | **Bag** | 7 | | BDT | |
| **c** | Supply:- Sand | **Cft** | 50 | | BDT | |
| **d** | Cutting ,fitting and fixing labour charges | **No.** | 20 | | BDT | |
| **F** | **Supply and fitting with labour cost:- (35' x22' 3'') Mass concrete casting(1:2:4) for Activity Floor NCF finished as per EIC direction.** | | | | | |
| **1** | **Supply:- Cement** | Bag | 34 | | BDT | |
| **2** | **Supply:- Sand** | Cft | 90 | | BDT | |
| **3** | **Supply:- 0.75 size Brick chips** | Cft | 172 | | BDT | |
| **4** | **Cutting ,fitting and fixing labour charges** | No. | 15 | | BDT | |
| **G** | **Column:-(30 Pc) Iner and outer** | | | | | |
| 1 | Supply:-3" dia, Metal pipe (3mm plate thickness) | PC | 36 | | BDT | |
| 2 | **(1 'x 1 'x 2.5') column Base CC casting ( 30 Pc.)** | | | | | |
| a | supply :- Cement | Bag | 13 | | BDT | |
| b | supply :- 0.75 size brick chips | Cft | 65 | | BDT | |
| c | supply :- Sand | Cft | 35 | | BDT | |
| d | Cutting, Fitting and Fixing labour Charges | No. | 10 | | BDT | |

| | | | | | | |
|---|---|---|---|---|---|---|
| **H** | **CGI Sheet Fence( Iner and Outer) and Roof.** | | | | | |
| 1 | **Supply :-** 0.33mm CGI Sheet(Dhewtin)(height 7'xWidth 2') for Roofing,Outer wall fence,inside Partion wall fence and Boundary Wall Fence and two entry door's shade as per EIC direction. | PC | 210 | | BDT | |
| 2 | **Supply :- (**2"x 2") Angle for wall fence horizantal batten and Roof Purlin as per EIC direction | RFT | 1032 | | BDT | |
| 3 | **Supply :- (**2.5" x2.5") Angle for Roof Rafter,Beam as per EIC direction | RFT | 940 | | BDT | |
| 4 | Cutting, Fitting and Fixing labour Charges | No. | 30 | | BDT | |
| **I** | **Door and Window:-** | | | | | |
| 1 | **Supply and fitting with labour cost:** Door (0.33mm Blue iron sheet,wooden frame,hinges,nails,Hasbolt) (3.0'x7') as per EIC direction | PC | 2 | | BDT | |
| 2 | **Supply and fitting with labour cost:** Door (0.33mm Blue iron sheet,wooden frame,hinges,nails,Good quality Hasbolt with Lock and key) (2.5'x7') as per EIC direction | PC | 4 | | BDT | |
| 3 | **Supply and fitting with labour cost:** Window(0.42mm Blue iron sheet,wooden frame,hinges,nails,Good quality Chitkani (2'x2') as per EIC direction | PC | 4 | | BDT | |
| **J** | **Walk way (100 sft.) cement bonding withNCF** | | | | | |
| 1 | Supply and fitting with labour cost: Single layer BFS with 3" sand filling , as per EIC direction | SFT | 100 | | BDT | |
| 2 | Supply:- cement | Bag | 3 | | BDT | |
| 3 | Cutting ,Fitting and Fixing labour charges | No. | 6 | | BDT | |
| **K** | **Drainage system(110 feet long):- Single layer BFS with 3'' sand filling , 5'' brick wall with Cement morter bonding , Plasterv and NCF finished sft. as per EIC direction** | | | | | |
| 1 | Supply :-Brick | Pc | 2000 | | BDT | |
| 2 | Supply :-Sand | Cft | 70 | | BDT | |
| 3 | Supply :- Cement | Bag | 8 | | BDT | |
| 4 | Cutting ,Fitting and Fixing labour charges | No. | 20 | | BDT | |
| | **Inc. Vat & Tax** | | | | **Total Cost** | |