Annex-15
BOQ for Metal Boundary Fence,Walkway Drainage, Main Structure and General Repairing.
Location:-Camp-26 -WGFS (shalbon)

S/N	Descriptions	Unit / Form	Quantity	Unit Price	Currency	Total Amount
A	**Boundary Fence(214 feet long) :-(MS Pipe,Angla and Dhewtin):-**					
1	Supply:- 2" dia and 9 feet long MS pipe (3mm plate thickness) as Column-(38 pc)	RFT	342		BDT	
2	**Column Base CC Casting (10''x 15'' x20'')**				BDT	
a	Supply :-Cement :-	Bag	13		BDT	
b	Supply :-Sand	Cft	35		BDT	
c	Supply :- 0.75 size Brick Chips.	Cft	70		BDT	
3	Supply : 7 feet high x 2' wide and 214 feet long Dhewtin Fence with Entry Gate.	PC	110		BDT	
4	Supply :1.5" x1.5" Angle (4 mm plate thickness) for horizantal support at top, middle and bottom.with a entry gate and 3'long angular support to each Column .	RFT	786		BDT	
5	Supply :- "J"Hook with nut for fixing up Dhewtin with angls.	PC	700		BDT	
6	Cutting, Fitting and Fixing Labour charges	No.	30		BDT	
B	**Walk way:(136' x3.5'=476sft):-Single Layer BFS including 4" Sand Filling with Cement mortar Plastering with NCF**					
1	Supply:- Cement	Bag	10		BDT	
2	Supply:- Sand	Cft	220		BDT	
3	Cutting, Fitting and Fixing Labour charges	No.	16		BDT	
C	**Gneneral Repairing:-**				BDT	
1	Supply:- Wood (2.5"x 1.25"x 8'=12 pc)for Door(Toilet,Store,Kitchen)	SFT	2		BDT	
2	Supply :- Kitchen 3" Borak Bamboo Column with Horizantal Batton.	PC	4		BDT	
3	Supply:- GI wire / Nails	LS	1		BDT	

4	Supply:- Kitchen Fence 7'x2' Dhewtin	PC	20		BDT	
5	Supply :-Door/window Chitkani	PC	12		BDT	
6	Supply :-Door Hingh (Kobza)	PC	12		BDT	
7	Supply :-Cement :-	Bag	10		BDT	
	Supply :-Sand	Cft	100		BDT	
8	Cutting, Fitting and Fixing Labour charges	No.	16		BDT	
D	**Drainage (L-120' x W-10'' x H-10'')**					
1	Supply:- :Brick	PC	**1500**		BDT	
2	Supply:- Cement	Bag	**13**		BDT	
3	Supply:- Sand	Cft	**150**		BDT	
4	Cutting, Fitting and Fixing Labour charges	No.	**20**		BDT	
E	**Main Structure's Metal Column(36 Pc) and Trass:-**					
1	Supply,20' Long, 3" dia metal Pipe(4mm Plate Thickness)	Rft	**492**		BDT	
2	Supply:- 2.5" x 2.5" Angle with 4mm plate thickness	Rft	**1188**		BDT	
3	Cutting, Fitting and Fixing Labour charges	No.	**35**		BDT	
3	**Column Base CC Casting (1'x 1' x2') (36 Block)**					
1	Supply :- : Brick	Bag	12		BDT	
2	Supply :- Cement	Cft	32		BDT	
3	Supply :- 0.75 size Brick Chips.	Cft	65		BDT	
4	Cutting, Fitting and Fixing Labour charges	No.	**35**		BDT	
F	**Angle with CGI Sheet iner and outer fence:-**					
1	Supply:- : 8 feet high x 2' wide and 214 feet long Dhewtin Fence with Entry Gate.	Pc	**150**		BDT	
2	Supply:- 1.5" x1.5" Angle (4 mm plate thickness) for horizantal support at top, middle and bottom.with a entry gate and 3'long angular support to each Column .	Rft	**900**		BDT	
3	Supply :- :"J"Hook with nut for fixing up Dhewtin with angls.	PC	650		BDT	
4	Cutting, Fitting and Fixing Labour charges	No.	30		BDT	
G	Electrical	Package	1		BDT	
	Inc Vat & Tax			**Total Cost**		