Annex-5
BOQ for Roof, Floor amd Latrine Repairing Work
At Camp-27, Nature Park, MPC,Teknaf

Sl No.	Description	Unit / Form	Quantity	Unit Price	Currency	Total Amount
A	**Flooring:- (30' x20'=600 Sft)**					
1	Mass concrete(30' x20' x3"= 150 Cft.) casting(1:2:4) for Activity Floor NCF finished as per EIC direction.					
a	Supply:- 3/4" size Brick Chips	**Cft**	130		BDT	
b	Supply:- Sand	**Cft**	65		BDT	
c	Supply:- Cement	**Bag**	26		BDT	
d	Cutting , Fitting and Fixing Labour Charges	**No.**	25		BDT	
B	**Roof covering (leakage) :- (34'x 26')**					
1	Supply : - 3" Borak bamboo 20'-0" long - For Rufter	pc	**10**		BDT	
2	Supply, fitting with Labour cost : 1.5" Muli Bamboo (1'x1') gridding (Purlin).	pc	**80**		BDT	
3	Supply:-t : 0.18 mm Polythene Sheet (Tarpoulin)	Sft	**884**		BDT	
4	Supply, fitting with Labour cost : 6 mm nylon rope	kg	**5**		BDT	
5	Supply, fitting with Labour cost : 3 mm nylon rope	kg	**2**		BDT	
6	Cutting , Fitting and Fixing Labour Charges	No.	10		BDT	
C	**Latrine Repairiring**					
1	Supply : -New Low Pan	Pc	1		BDT	
2	Supply : -4" Dia PVC Pipe	Rft	10		BDT	
3	Supply : - 4" Elbow	Pc	2		BDT	
4	Supply : - Water Seal (Gum)	Tube	1		BDT	
5	Waste Pit Cleaning	Package	1		BDT	
4	Cutting , Fitting and Fixing Labour Charges	No.	3		BDT	
D	**Electrical -Electronic Repairing:**					
1	Repair, Fitting and fixing of Two no of Stand Fan ,One Ceiling Fan and One Switch Board with Technician Charges	Package	1		BDT	
E	Carrying, Lifting ,Loading/Unloading of Donneted Items to site	Package	1		BDT	
	Inc. Vat and Tax				**Total Cost:-**	